



- 1** Compressor Station 185  
- Add one 25,000 HP electric motor driven compressor
- 2** Compressor Station 166 (To Be Constructed 2015)  
- Install two Solar Taurus 70 (10,915 ISO HP each) and three bays of cooling  
- Re-wheel two existing Solar Taurus 70 compressor units
- 3** Greensville Lateral Take-Off  
- Tie-in at MP 5.2 of the Brunswick Lateral  
- Install pig launcher
- 4** Proposed Greensville Lateral  
- Build 4.7 mile 24" lateral from MP 0.0 to 4.7
- 5** Meter Station  
- Construct 250 Mdt/d meter station, install heaters and pig receiver at MP 4.7

## Virginia Southside Expansion Project II Legend

- Existing Transco Pipelines
- South Virginia Lateral - B Line (To Be Constructed 2015)
- Brunswick Lateral (To Be Constructed 2015)
- Proposed Greensville Lateral
- Existing Compressor Station
- Compressor Station 166 (To Be Constructed 2015)
- Proposed Meter Station

FOR DISCUSSION PURPOSES ONLY  
SUBJECT TO CHANGE

**FIGURE 1.0**  
**PROJECT OVERVIEW MAP**  
**VIRGINIA SOUTHSIDE EXPANSION PROJECT II**  
 TRANSCONTINENTAL GAS  
 PIPE LINE COMPANY, LLC  
 JULY 1, 2014